

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P., Bengaluru - 64

APPROVED TENDER SCHEDULE - 'B'

Name of Work: **Improvements of drain and RCC road in near Kanaka nagara in ward No 04**

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP	
				Rate	Rate in Words
1	KSRB 300-1 Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average fill up to 1.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no 19.1 Page no 138, PWD SR 2014-15)	Cum	600	75.60	Rupess seventy five and paise sixty only
2	KSRM 300-58, Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occurring during rolling including cost of all labour, H.O.M of machinery complete as per specifications, MORTH Chapter 3	Sqm	1149.50	4.48	Rupess four and paise forty eight only
3	KSRB 4-1.3 Providing and laying in position plain cement concrete of mix 1:1.5:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.55cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15cm, thick, well compacted in foundation, including cost of all materials, labour, H.O.M of machinery, curing complete as per specifications, Specification no KBS4.1.4.2 (Item no 4.3, Page no 12, PWD SR 2014-15)	Cum	180.26	4847.04	Rupess four thousand eight hundred forty seven and paise four only
4	KSRD 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with super plasticiser @ 3lit conforming etc as per specification & direction of the engineer incharge of work (pwd sr 2014-15, para 13, para 4, 11)	Cum	120.18	6065.28	Rupess six thousand sixty five and paise twenty eight only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP	
				Rate	Rate in Words
5	KSRB 492: Providing L.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications. Specification no KBS 4.5.3, TMT bars Fe550/pwd sr 2014-15, p.no 17, s.no 4.46)	Qtl	42.06	7905.60	Rupass seven thousand nine hundred five and paise sixty only
6	Vacuum de-watering with vacuum pump and suction mat and compaction with skin roller clubbed with floating disc including cost of generator, H.O.M of machinery, Secord Villeroy, Power Floater, blade and disc etc., with all lead and lift.(P.No 171, L.No 22.7)	Sqm	1201.75	97.20	Rupass ninety seven and paise twenty only
7	Providing groove cutting for width of 5 mm to 10mm and depth 80mm-100 mm including cost of cutting machine, generator & H.O.M of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot bitumen fillers, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications for concrete payment, (P.No 172, L.No 22.8)	Kmt	695.00	124.20	Rupass one hundred twenty four and paise twenty only
8	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/anker/ Moorum KSRRB M100-1-Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for handling and return trip complete as per specifications (item no 17.1 Pace no 130, PWD SR 2014-15)	Cum	600.88	68.04	Rupass sixty eight and paise four only

Signature of the Contractor


EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010


Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-54.